

Plantation Acres Improvement District Broward County Florida

1701 NW 112th Avenue, Plantation, FL 33323 AGENDA March 24, 2022

Call to Order 7:00 P.M.

Pledge of Allegiance

Invocation

Roll Call

Approval of Attendance of Commissioners by Social Media or Telephone

Approval of Minutes

Public Comment

Staff Reports

- I. Administrator's Report
- II. Attorney's Report
- III. Engineer's Report
 - A. CONSENT ITEMS

None

B. QUASI-JUDICIAL ITEMS

The items in this section are quasi-judicial in nature. If you wish to object or comment upon any of these items, you must be sworn before addressing the Board of Commissioners, and if you wish to address the Board, you may be subject to cross-examination. If you refuse to submit to cross-examination, the Board of Commissioners will not consider what you have said in its final deliberations.

- B1. Flamingo Plaza Site Improvements (C2111.01) Approval
- C. BOARD ACTION ITEMS

None

D. DISCUSSION ITEMS

D1.	Pump Station Number 3 Rehabilitation (D1707.01-3) Update
D2.	20-Year Needs Analysis (D2109.01) Update
D3.	Swale Obstruction Evaluation (D2201.01) Discussion
D4.	Funding for Improvements (D2201.01)
D5.	Permit Activity (D9408.02 & D9408.03)
D6.	Violation Activity (D9611.01)
D4. D5.	Swale Obstruction Evaluation (D2201.01) Discussion Funding for Improvements (D2201.01) Discussion Permit Activity (D9408.02 & D9408.03) Summar

IV. District Manager's Agenda

Old Business

- New Business
- Adjournment

Action Required:	Board Approval (Quasi-Judicial)
Item Description:	Flamingo Plaza Site Improvements Plan
P.A.I.D. Number:	<u>C2111.01</u>
Attachments:	Construction Plan (11" x 17" reduced copy) Permit Application
Summary:	This item is for the approval of the improvement plans serving the existing plaza on the southeast corner of Flamingo Road and W. Sunrise Boulevard. The plan involves minor site improvements such as demolition of existing asphalt, landscaping, concrete sidewalk and curbing and reconstruction of asphalt parking spaces, landscaping, concrete sidewalk and curbing in preparation for a new grocery tenant within the project boundary area.
	Pervious area slightly increases as minor landscaping is improved; whereas the overall impervious area slightly decreases.
	The paving, grading and drainage plan meets the criteria of the District.
Recommendation:	APPROVE
Comments:	
Prepared by: <u>BMP</u>	Date: 3/14/2022 2022-03-14 Staff Report.wpd

SOUTH FLORIDA WATER MANAGEMENT DISTRICT (SFWMD) AND PLANTATION ACRES IMPROVEMENT DISTRICT (PAID) PLANS FOR

PROJECT LOCATION (BROWARD COUNTY)

PROJECT TEAM

OWNER/DEVELOPER DACAR MANAGEMENT DANIA BEACH, FL 33004 (954) 505-550

ARCHITECT


SEAN HERRING LA ARCHITECTS 7800 WASHINGTON, SUITE 600 HOUSTON, TX 77007 (713) 600-3600

SURVEYOR PULICE LAND SURVEYORS, INC. 5381 NOB HILL ROAD SUNRISE, FL 33351 (954) 572-1777

PROJECT LOCATION

CIVIL ENGINEER GREG D. WILFONG, P.E. KIMLEY-HORN AND ASSOCIATES, INC 4TH STREET, SUITE 200 RO BEACH, FL 32960 WILFONG@ KIMLEY-HORN.COM

LAND USE ATTORNEY BONNIE MISKEL, ESQ. DUNAY, MISKEL, BACKMAN AND BLATTNER, LLP 14 S.E 4 STREET, SUITE 36 BOCA RATON, FL 33432 (561) 405-3321



N.T.S.

LIST OF CONTACTS

STORMWATER

PLANTATION ACRES IMPROVEMENT DISTRICT 111 NE 44TH STREET OAKLAND PARK, FL 33334 954-771-7440 CONTACT: WERNER T. VAUGHAN, PE WINNINGHAM AND FRADLEY, INC.

WATER & SEWER CITY OF PLANTATION UTILITIES DIVISION 400 NW 73RD AVENUE PLANTATION, FL 33317 954-797-2159 CONTACT: JOHN ADAMS

FIRE

CITY OF PLANTATION FIRE DEPARTMENT 550 NW 65TH AVENUE PLANTATION, FL 33317 954-797**-**2150 CONTACT: TONY MARTINS FIRE MARSHAL

PLANNING AND ZONING CITY OF PLANTATION 401 NW 70TH TERRACE PLANTATION, FL 33317 954-797-2266 CONTACT: SHAWN LAMEY PRINCIPAL PLANNER, PZED

BUILDING DEPARTMENT

CITY OF PLANTATION 400 NW 73RD AVENUE PLANTATION, FL 33317 954-797-2290 CONTACT: CARMEN HURLBUT ASSISTANT BUILDING OFFICIAL

PUBLIC WORKS CITY OF PLANTATION 750 NW 91ST AVENUE PLANTATION, FL 33324 954-414-7395 CONTACT: INDYLI BROWN LANDSCAPE DIVISION

3020 NW 19TH STREET 954-717-1436 ASSOCIATE ENGINEER

AT&T 8601 W SUNRISE BLVD PLANTATION, FL 33322 954-476-2916

5101 NW 21ST AVE 813-635-1500

FLAMINGO PLAZA

LOCATED AT 12300 WEST SUNRISE BOULEVARD CITY OF PLANTATION, BROWARD COUNTY, FLORIDA 33323 SECTION 36, TOWNSHIP 49S, RANGE 40E

> ELECTRIC PROVIDER FLORIDA POWER AND LIGHT FORT LAUDERDALE, FL 33311 CONTACT: MORGAN JOHNSON


TELEPHONE PROVIDER

NATURAL GAS PROVIDER

FORT LAUDERDALE, FL 33309

PREPARED BY: **Kimley**»Horn

	Sheet List Table
Sheet Number	Sheet Title
C-000	COVER SHEET
1 OF 1	BOUNDARY AND TOPOGRAPHIC SURVEY
C-100	GENERAL NOTES
C-200	DEMOLITION AND EROSION CONTROL PLAN
C-201	EROSION CONTROL PLAN PHASE II
C-202	EROSION CONTROL NOTES AND DETAILS
C-204	EROSION CONTROL NOTES AND DETAILS
C-300	SITE PLAN
C-400	PAVING GRADING AND DRAINAGE PLAN
C-401	PAVING GRADING AND DRAINAGE DETAILS
C-402	PAVEMENT DELINEATION PLAN




SHEET NUMBER

C-000

Always call 811 two full business days before you dig to have underground utilities located and marked.

Sunshine gill.com



LEGAL DESCRIPTION:

PARCEL 1: THAT PORTION OF TRACT A, PLAT OF "D & C PROPERTIES - SUNRISE AND FLAMINGO", ACCORDING TO THE PLAT THEREOF AS RECORDED IN PLAT BOOK 147, PAGE 21, PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA, DESCRIBED AS FOLLOWS:

BEGINNING AT THE SOUTHWEST CORNER OF SAID TRACT A; THENCE RUN NORTH 00'09'22" WEST (ON A PLAT BEARING) 131.64 FEET ALONG THE WESTERLY BOUNDARY OF SAID TRACT A TO A POINT OF INTERSECTION; THENCE RUN NORTH 03'50'05" EAST 143.68 FEET ALONG SAID WESTERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 00'09'22" WEST 146.17 FEET ALONG SAID WESTERLY BOUNDARY; THENCE RUN NORTH 89'35'44" EAST 251.93 FEET; THENCE RUN NORTH 00'09'22" WEST 146.17 FEET ALONG SAID WESTERLY BOUNDARY; THENCE RUN NORTH 89'35'44" EAST 171.31 FEET TO AN INTERSECTION WITH THE NORTHERLY BOUNDARY OF SAID TRACT A; THENCE RUN NORTH 89'35'44" EAST 8.85 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 8.85 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 8.85 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 8.85 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 8.85 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 8.85 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOUNDARY TO A POINT OF INTERSECTION; THENCE RUN NORTH 89'35'44" EAST 105 FEET ALONG SAID NORTHERLY BOU SOUTH 83'33'42" EAST 100.72 FEET ALONG SAID NORTHERLY BOUNDARY TO THE NORTHEAST CORNER OF SAID TRACT A; THENCE RUN SOUTH 00'09'02" EAST 592.20 FEET TO THE SOUTHEAST CORNER OF SAID TRACT A, THENCE RUN SOUTH 89'34'35" WEST 640.73 FEET ALONG THE SOUTH BOUNDARY OF SAID TRACT A, TO THE POINT OF BEGINNING.


PARCEL 2: (EASEMENT INTEREST) TOGETHER WITH NON-EXCLUSIVE EASEMENT RIGHTS FOR THE BENEFIT OF PARCEL 1, DESCRIBED ABOVE, AS CONTAINED IN THAT CERTAIN EASEMENT AGREEMENT BY AND BETWEEN D & C - SUNRISE & FLAMINGO, LTD., A FLORIDA LIMITED PARTNERSHIP AND CRD ASSOCIATES, A FLORIDA GENERAL PARTNERSHIP DATED JULY 10, 1990 AND RECORDED FEBRUARY 15, 1991 IN O.R.B. 18148, PAGE 837, TOGETHER WITH FIRST AMENDMENT TO EASEMENT AGREEMENT RECORDED IN O.R.B. 27670, PAGE 813, BOTH TOF THE FUBLIC RECORDS OF BROWARD COUNTY, FLORIDA. PARCEL 3: (EASEMENT INTEREST)

TOGETHER WITH NON-EXCLUSIVE EASEMENT RIGHT(S) FOR THE BENEFIT OF PARCEL 1, DESCRIBED ABOVE, AS CONTAINED IN THAT CERTAIN EASEMENT BY AND BETWEEN FORT LAUDERDALE BAPTIST TEMPLE, INC., A FLORIDA CORPORATION; BROWARD CHRISTIAN SCHOOLS, INC., A FLORIDA CORPORATION AND D & C -SUNRISE & FLAMINGO, LTD., A FLORIDA LIMITED PARTNERSHIP DATED OCTOBER 5, 1995 AND RECORDED JANUARY 23, 1996 IN O.R.B. 24409, PAGE 641, TOGETHER WITH ADDENDUM TO EASEMENT RECORDED IN O.R.B. 26517, PAGE 493, BOTH OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.

PARCEL 4: (EASEMENT INTEREST) TOGETHER WITH NON-EXCLUSIVE EASEMENT RIGHT(S) FOR THE BENEFIT OF PARCEL 1, DESCRIBED ABOVE, AS CONTAINED IN THAT CERTAIN EASEMENT BY AND AMONG PLANTATION ACRES IMPROVEMENT DISTRICT, D & C - SUNRISE & FLAMINGO, LTD., A FLORIDA LIMITED PARTNERSHIP, BROWARD CHRISTIAN SCHOOLS, INC., A FLORIDA CORPORATION AND THE FORT LAUDERDALE BAPTIST TEMPLE, INC., A FLORIDA CORPORATION, DATED APRIL 15, 1997 AND RECORDED JUNE 4, 1997 IN O.R.B. 26517, PAGE 504, OF THE PUBLIC RECORDS OF BROWARD COUNTY, FLORIDA.

RESTRICTIVE USE AGREEMENT TO ASSURE TEMPORARY UNIFIED CONTROL IN O.R.B. 21877, PAGE 283 APPLIES TO THIS SITE BUT CANNOT BE

ACCORDANCE WITH THE 2021 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 7(a), 8, 9 & 11 OF



GENERAL CONSTRUCTION NOTES

1. THE CONTRACTOR AND SUBCONTRACTORS SHALL OBTAIN A COPY OF THE FLORIDA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (LATEST EDITION) AND BECOME FAMILIAR WITH THE CONTENTS PRIOR TO COMMENCING WORK, AND, UNLESS OTHERWISE NOTED, ALL WORK SHALL CONFORM AS APPLICABLE TO THESE STANDARDS AND SPECIFICATIONS.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL MATERIAL AND LABOR TO CONSTRUCT THE FACILITY AS SHOWN AND DESCRIBED IN THE CONSTRUCTION DOCUMENTS IN ACCORDANCE WITH THE APPROPRIATE APPROVING AUTHORITIES, SPECIFICATIONS AND REQUIREMENTS. CONTRACTOR SHALL CLEAR AND GRUB ALL AREAS UNLESS OTHERWISE INDICATED, REMOVING TREES, STUMPS, ROOTS, MUCK, EXISTING PAVEMENT AND ALL OTHER DELETERIOUS MATERIAL.

EXISTING UTILITIES SHOWN ARE LOCATED ACCORDING TO THE INFORMATION AVAILABLE TO THE ENGINEER AT THE TIME OF THE TOPOGRAPHIC SURVEY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR THE ENGINEER. GUARANTEE IS NOT MADE THAT ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN OR THAT THE LOCATION OF THOSE SHOWN ARE ENTIRELY ACCURATE. FINDING THE ACTUAL LOCATION OF ANY EXISTING UTILITIES IS THE CONTRACTOR'S RESPONSIBILITY AND SHALL BE DONE BEFORE HE COMMENCES ANY WORK IN THE VICINITY. FURTHERMORE, THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES DUE TO THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. THE OWNER OR ENGINEER WILL AS SUME NO LIABILITY FOR ANY DAMAGES SUSTAINED OR COST INCURRED BECAUSE OF THE OPERATIONS IN THE VICINITY OF EXISTING UTILITIES OR STRUCTURES, NOR FOR TEMPORARY BRACING AND SHORING OF SAME. IF IT IS NECESSARY TO SHORE, BRACE, SWING OR RELOCATE A UTILITY, THE UTILITY COMPANY OR DEPARTMENT AFFECTED SHALL BE CONTACTED AND THEIR PERMISSION OBTAINED REGARDING THE METHOD TO USE FOR SUCH WORK.

4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES WHICH MAY HAVE BURIED OR AERIAL UTILITIES WITHIN OR NEAR THE CONSTRUCTION AREA BEFORE COMMENCING WORK. THE CONTRACTOR SHALL PROVIDE 48 HOURS MINIMUM NOTICE TO ALL UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION. A LIST OF THE UTILITY COMPANIES WHICH THE CONTRACTOR MUST CALL BEFORE COMMENCING WORK IS PROVIDED ON THE COVER SHEET OF THESE CONSTRUCTION PLANS. THIS LIST SERVES AS A GUIDE ONLY AND IS NOT INTENDED TO LIMIT THE UTILITY COMPANIES WHICH THE CONTRACTOR MAY WISH TO NOTIFY.

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED CONSTRUCTION PERMITS AND BONDS IF REQUIRED PRIOR TO CONSTRUCTION.
- 6. THE CONTRACTOR SHALL HAVE AVAILABLE AT THE JOB SITE AT ALL TIMES ONE COPY OF THE CONSTRUCTION DOCUMENTS INCLUDING PLANS, SPECIFICATIONS, AND SPECIAL CONDITIONS AND COPIES OF ANY REQUIRED CONSTRUCTION PERMITS.
- ANY DISCREPANCIES ON THE DRAWINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER AND ENGINEER BEFORE COMMENCING WORK. NO FIELD CHANGES OR DEVIATIONS FROM DESIGN ARE TO BE MADE WITHOUT PRIOR APPROVAL OF THE OWNER AND NOTIFICATION TO THE ENGINEER.
- 8. ALL COPIES OF COMPACTION, CONCRETE AND OTHER REQUIRED TEST RESULTS ARE TO BE SENT TO THE OWNER AND DESIGN ENGINEER OF RECORD DIRECTLY FROM THE **TESTING AGENCY.**
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING TO THE ENGINEER A CERTIFIED RECORD SURVEY SIGNED AND SEALED BY A PROFESSIONAL LAND SURVEYOR REGISTERED IN THE STATE OF FLORIDA DEPICTING THE ACTUAL FIELD LOCATION OF ALL CONSTRUCTED IMPROVEMENTS THAT ARE REQUIRED BY THE JURISDICTIONAL AGENCIES FOR THE CERTIFICATION PROCESS. ALL SURVEY COSTS WILL BE THE CONTRACTORS RESPONSIBILITY.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DOCUMENTING AND MAINTAINING AS-BUILT INFORMATION WHICH SHALL BE RECORDED AS CONSTRUCTION PROGRESSES OR AT THE COMPLETION OF APPROPRIATE CONSTRUCTION INTERVALS AND SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS TO THE OWNER FOR THE PURPOSE OF CERTIFICATION TO JURISDICTIONAL AGENCIES AS REQUIRED. ALL AS-BUILT DATA SHALL BE COLLECTED BY A STATE OF FLORIDA PROFESSIONAL LAND SURVEYOR WHOSE SERVICES ARE ENGAGED BY THE CONTRACTOR.
- 11. ANY WELLS DISCOVERED ON SITE THAT WILL HAVE NO USE MUST BE PLUGGED BY A LICENSED WELL DRILLING CONTRACTOR IN A MANNER APPROVED BY ALL JURISDICTIONAL AGENCIES. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY WELL ABANDONMENT PERMITS REQUIRED.
- 12. ANY WELL DISCOVERED DURING EARTH MOVING OR EXCAVATION SHALL BE REPORTED TO THE APPROPRIATE JURISDICTIONAL AGENCIES WITHIN 24 HOURS AFTER DISCOVERY IS MADE.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, THE CONTRACTOR SHALL NOTIFY THE OWNER PRIOR TO INSTALLATION OF ANY PORTION OF THE SITE WORK THAT WOULD BE AFFECTED. FAILURE TO NOTIFY OWNER OF AN IDENTIFIABLE CONFLICT PRIOR TO PROCEEDING WITH INSTALLATION RELIEVES OWNER OF ANY OBLIGATION TO PAY FOR A RELATED CHANGE ORDER.

DEMOLITION NOTES

1. ALL MATERIAL REMOVED FROM THIS SITE BY THE CONTRACTOR SHALL BE DISPOSED OF BY THE CONTRACTOR IN A LEGAL MANNER.

2. REFER TO THE TOPOGRAPHIC SURVEY FOR ADDITIONAL DETAILS OF EXISTING STRUCTURES, ETC., LOCATED WITHIN THE PROJECT SITE. UNLESS OTHERWISE NOTED, ALL EXISTING BUILDINGS, STRUCTURES, SLABS, CONCRETE, ASPHALT, DEBRIS PILES, SIGNS, AND ALL APPURTENANCES ARE TO BE REMOVED FROM THE SITE BY THE CONTRACTOR AND PROPERLY DISPOSED OF IN A LEGAL MANNER AS PART OF THIS CONTRACT. SOME ITEMS TO BE REMOVED MAY NOT BE DEPICTED ON THE TOPOGRAPHIC SURVEY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VISIT THE SITE AND DETERMINE THE FULL EXTENT OF ITEMS TO BE REMOVED. IF ANY ITEMS ARE IN QUESTION, THE CONTRACTOR SHALL CONTACT THE OWNER PRIOR TO REMOVAL OF SAID ITEMS.

3. THE CONTRACTOR SHALL REFER TO THE DEMOLITION PLAN FOR DEMOLITION/PRESERVATION OF EXISTING TREES. ALL TREES NOT SPECIFICALLY SHOWN TO BE PRESERVED OR RELOCATED SHALL BE REMOVED AS A PART OF THIS CONTRACT. TREE PROTECTION FENCING SHALL BE INSTALLED PRIOR TO ANY DEMOLITION.

PAVING, GRADING AND DRAINAGE NOTES

- EDITION) IF NOT COVERED BY LOCAL OR COUNTY REGULATIONS.
- SHALL BE REGRADED AND SODDED.
- STRINGENT SHALL GOVERN.
- OTHERWISE ON THE LANDSCAPE PLAN.
- EXISTING OR AS INDICATED.
- PAVEMENT UNLESS OTHERWISE INDICATED.
- DESIGN ENGINEER PRIOR TO ANY EXCAVATION.
- LANDSCAPED AREAS BUT ONLY AS DIRECTED BY THE OWNER.
- AGREEMENT, THE MOST STRINGENT SHALL GOVERN.
- AND MULCHED AS SHOWN ON THE LANDSCAPING PLAN.
- OTHERWISE SHOWN.
- PROTECTION.
- IN CHAPTER 17-302, FLORIDA ADMINISTRATIVE CODE.
- WITHIN 48 HOURS OF COMPLETING FINAL GRADING, AND AT ANY OTHER TIME AS NECESSARY, TO PREVENT EROSION, SEDIMENTATION OR TURBID DISCHARGES.
- MANAGEMENT DISTRICT REPRESENTATIVES.
- MANNER.
- MANUFACTURER'S RECOMMENDATIONS.

1. ALL PAVING, CONSTRUCTION, MATERIALS, AND WORKMANSHIP WITHIN COUNTY'S RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH LOCAL OR COUNTY SPECIFICATIONS AND STANDARDS (LATEST EDITION) OR FDOT SPECIFICATIONS AND STANDARDS (LATEST

2. ALL UNPAVED AREAS IN EXISTING RIGHTS-OF-WAY DISTURIED BY CONSTRUCTION

3. TRAFFIC CONTROL ON ALL FDOT, LOCAL AND COUNTY RIGHTS-OF-WAY SHALL MEET THE REQUIREMENTS OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (U.S. DOT/FHA) AND THE REQUIREMENTS OF THE STATE AND ANY LOCAL AGENCY HAVING JURISDICTION. IN THE EVENT THAT THE CONTRACT DOCUMENTS AND THE JURISDICTIONAL AGENCY REQUIREMENTS ARE NOT IN AGREEMENT, THE MOST

4. THE CONTRACTOR SHALL GRADE THE SITE TO THE ELEVATIONS INDICATED AND SHALL REGRADE WASHOUTS WHERE THEY OCCUR AFTER EVERY RAINFALL UNTIL A GRASS STAND IS WELL ESTABLISHED OR ADEQUATE STABILIZATION OCCURS.

5. ALL OPEN AREAS WITHIN THE PROJECT SITE SHALL BE SOGDED UNLESS INDICATED

6. ALL AREAS INDICATED AS PAVEMENT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE TYPICAL PAVEMENT SECTIONS AS INDICATED ON THE DRAWINGS.

7. WHERE EXISTING PAVEMENT IS INDICATED TO BE REMOVED AND REPLACED. THE CONTRACTOR SHALL SAW CUT A MINIMUM 2" DEEP FOR A SMOOTH AND STRAIGHT JOINT AND REPLACE THE PAVEMENT WITH THE SAME TYPE AND DEPTH OF MATERIAL AS

8. WHERE NEW PAVEMENT MEETS THE EXISTING PAVEMENT, THE CONTRACTOR SHALL SAW CUT THE EXISTING PAVEMENT A MINIMUM 2" DEEP FOR A SMOOTH AND STRAIGHT JOINT AND MATCH THE EXISTING PAVEMENT ELEVATION WITH THE PROPOSED

9. THE CONTRACTOR SHALL INSTALL FILTER FABRIC OVER ALL DRAINAGE STRUCTURES FOR THE DURATION OF CONSTRUCTION AND UNTIL ACCEPTANCE OF THE PROJECT BY THE OWNER. ALL DRAINAGE STRUCTURES SHALL BE CLEANED OF DEBRIS AS REQUIRED DURING AND AT THE END OF CONSTRUCTION TO PROVIDE POSITIVE DRAINAGE FLOWS.

10. IF DEWATERING IS REQUIRED, THE CONTRACTOR SHALL OBTAIN ANY APPLICABLE REQUIRED PERMITS. THE CONTRACTOR IS TO COORDINATE WITH THE OWNER AND THE

11. STRIP TOPSOIL AND ORGANIC MATTER FROM ALL AREAS OF THE SITE AS REQUIRED. IN SOME CASES TOPSOIL MAY BE STOCKPILED ON SITE FOR PLACEMENT WITHIN

12. FIELD DENSITY TESTS SHALL BE TAKEN AT INTERVALS IN ACCORDANCE WITH THE LOCAL JURISDICTIONAL AGENCY OR TO FDOT STANDARDS. IN THE EVENT THAT THE CONTRACT DOCUMENTS AND THE JURISDICTIONAL AGENCY REQUIREMENTS ARE NOT IN

13. ALL SLOPES AND AREAS DISTURBED BY CONSTRUCTION SHALL BE GRADED AS PER PLANS. THE AREAS SHALL THEN BE SODDED OR SEEDED AS SPECIFIED IN THE PLANS. FERTILIZED, MULCHED, WATERED AND MAINTAINED UNTIL HARDY GRASS GROWTH IS ESTABLISHED IN ALL AREAS. ANY AREAS DISTURBED FOR ANY REASON PRIOR TO FINAL ACCEPTANCE OF THE JOB SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER. ALL EARTHEN AREAS WILL BE SODDED OR SEEDED

14. ALL CUT OR FILL SLOPES SHALL BE 4 (HORIZONTAL) :1 (VERTICAL) OR FLATTER UNLESS

15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTROL OF DUST AND DIRT RISING AND SCATTERING IN THE AIR DURING CONSTRUCTION AND SHALL PROVIDE WATER SPRINKLING OR OTHER SUITABLE METHODS OF CONTROL THE CONTRACTOR SHALL COMPLY WITH ALL GOVERNING REGULATIONS PERTAINING TO ENVIRONMENTAL

16. THE CONTRACTOR SHALL TAKE ALL REQUIRED MEASURES TO CONTROL TURBIDITY, INCLUDING BUT NOT LIMITED TO THE INSTALLATION OF TURBIDITY BARRIERS AT ALL LOCATIONS WHERE THE POSSIBILITY OF TRANSFERRING SUSPENDED SOLIDS INTO THE RECEIVING WATER BODY EXISTS DUE TO THE PROPOSED WORK, TURBIDITY BARRIERS MUST BE MAINTAINED IN EFFECTIVE CONDITION AT ALL LOGATIONS UNTIL CONSTRUCTION IS COMPLETED AND DISTURBED SOIL AREAS ARE STABILIZED. THEREAFTER, THE CONTRACTOR MUST REMOVE THE BARRIERS, AT NO TIME SHALL THERE BE ANY OFF-SITE DISCHARGE WHICH VIOLATES THE WATER QUALITY STANDARDS

17. SOD, WHERE CALLED FOR, MUST BE INSTALLED AND MAINTAINED ON EXPOSED SLOPES

18. THE CONTRACTOR MUST REVIEW AND MAINTAIN A COPY OF THE ENVIRONMENTAL RESOURCE PERMIT COMPLETE WITH ALL CONDITIONS, ATTACHMENTS, EXHIBITS, AND PERMIT MODIFICATIONS IN GOOD CONDITION AT THE CONSTRUCTION SITE. THE COMPLETE PERMIT MUST BE AVAILABLE FOR REVIEW UPON REQUEST BY WATER

19. THE CONTRACTOR SHALL ENSURE THAT ISLAND PLANTING AREAS AND OTHER PLANTING AREAS ARE NOT COMPACTED AND DO NOT CONTAIN ROAD BASE MATERIALS. THE CONTRACTOR SHALL ALSO EXCAVATE AND REMOVE ALL UNDESIRABLE MATERIAL FROM ALL AREAS ON THE SITE TO BE PLANTED AND PROPERLY DISPOSED OF IN A LEGAL

20. THE CONTRACTOR SHALL INSTALL ALL UNDERGROUND STORM WATER PIPING PER

WATER AND SEWER UTILITY NOTES

1. THE CONTRACTOR SHALL CONSTRUCT GRAVITY SEWER LATERALS, MANHOLES GRAVITY SEWER LINES AND DOMESTIC WATER AND FIRE PROTECTION SYSTEM AS SHOWN ON THESE PLANS. THE CONTRACTOR SHALL FURNISH ALL NECESSARY MATERIALS, EQUIPMENT, MACHINERY, TOOLS, MEANS OF TRANSPORTATION AND LABOR NECESSARY TO COMPLETE THE WORK IN FULL AND COMPLETE ACCORDANCE WITH THE SHOWN, DESCRIBED AND REASONABLY INTENDED REQUIREMENTS OF THE CONTRACT DOCUMENTS AND JURISDICTIONAL AGENCY REQUIREMENTS. IN THE EVENT THAT THE CONTRACT DOCUMENTS AND THE JURISDICTIONAL AGENCY REQUIREMENTS ARE NOT IN AGREEMENT, THE MOST STRINGENT SHALL GOVERN.

- 2. ALL EXISTING UNDERGROUND UTILITY LOCATIONS SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS FOR UTILITY LOCATION AND COORDINATION IN ACCORDANCE WITH THE NOTES CONTAINED IN THE GENERAL CONSTRUCTION SECTION OF THIS SHEET.
- 3. THE CONTRACTOR SHALL RESTORE ALL DISTURBED VEGETATION IN KIND, UNLESS SHOWN OTHERWISE
- 4. DEFLECTION OF PIPE JOINTS AND CURVATURE OF PIPE SHALL NOT EXCEED THE MANUFACTURER'S SPECIFICATIONS. SECURELY CLOSE ALL OPEN ENDS OF PIPE AND FITTINGS WITH A WATERTIGHT PLUG WHEN WORK IS NOT IN PROGRESS. THE INTERIOR OF ALL PIPES SHALL BE CLEAN AND JOINT SURFACES WIPED CLEAN AND DRY AFTER THE PIPE HAS BEEN LOWERED INTO THE TRENCH. VALVES SHALL BE PLUMB AND LOCATED ACCORDING TO THE PLANS.
- 5. ALL PHASES OF INSTALLATION, INCLUDING UNLOADING, TRENCHING, LAYING AND BACK FILLING, SHALL BE DONE IN A FIRST CLASS WORKMANLIKE MANNER. ALL PIPE AND FITTINGS SHALL BE CAREFULLY STORED FOLLOWING MANUFACTURER'S RECOMMENDATIONS. CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE COATING OR LINING IN ANY D.I. PIPE FITTINGS. ANY PIPE OR FITTING WHICH IS DAMAGED OR WHICH HAS FLAWS OR IMPERFECTIONS WHICH, IN THE OPINION OF THE ENGINEER OR OWNER. RENDERS IT UNFIT FOR USE, SHALL NOT BE USED. ANY PIPE NOT SATISFACTORY FOR USE SHALL BE CLEARLY MARKED AND IMMEDIATELY REMOVED FROM THE JOB SITE, AND SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 6. WATER FOR FIRE FIGHTING SHALL BE AVAILABLE FOR USE PRIOR TO COMBUSTIBLES BEING BROUGHT ON SITE.
- 7. ALL UTILITY AND STORM DRAIN TRENCHES LOCATED UNDER AREAS TO RECEIVE PAVING SHALL BE COMPLETELY BACK FILLED IN ACCORDANCE WITH THE GOVERNING JURISDICTIONAL AGENCY'S SPECIFICATIONS. IN THE EVENT THAT THE CONTRACT DOCUMENTS AND THE JURISDICTIONAL AGENCY REQUIREMENTS ARE NOT IN AGREEMENT, THE MOST STRINGENT SHALL GOVERN.
- 8. UNDERGROUND LINES SHALL BE SURVEYED BY A STATE OF FLORIDA PROFESSIONAL LAND SURVEYOR PRIOR TO BACK FILLING.
- 9. CONTRACTOR SHALL PERFORM, AT HIS OWN EXPENSE, ANY AND ALL TESTS REQUIRED BY THE SPECIFICATIONS AND/OR ANY AGENCY HAVING JURISE/ICTION. THESE TESTS MAY INCLUDE, BUT MAY NOT BE LIMITED TO. INFILTRATION AND EXFILTRATION, TELEVISION INSPECTION AND A MANDREL TEST ON GRAVITY SEWER. A COPY OF THE TEST RESULTS SHALL BE PROVIDED TO THE UTILITY PROVIDER, OWNER AND JURISDICTIONAL AGENCY AS REQUIRED.

EROSION CONTROL NOTES

- 1. THE STORM WATER POLLUTION PREVENTION PLAN ("SWPPP") IS COMPRISED OF THE EROSION CONTROL PLAN, THE STANDARD DETAILS, THE PLAN NARRATIVE, ATTACHMENTS INCLUDED IN SPECIFICATIONS OF THE SWPPP, PLUS THE PERMIT AND ALL SUBSEQUENT REPORTS AND RELATED DOCUMENTS.
- 2. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN AND THE STATE OF FLORIDA NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM GENERAL PERMIT (NPDES PERMIT) AND BECOME FAMILIAR WITH THEIR CONTENTS.
- 3. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES AS REQUIRED BY THE SWPPP. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST TO THE OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION.
- 4. BEST MANAGEMENT PRACTICES (BMP'S) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY THE PERMITTING AGENCY OR OWNER.
- 5. EROSION CONTROL PLAN MUST CLEARLY DELINEATE ALL STATE WATERS. PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS MUST BE MAINTAINED ON SITE AT ALL TIMES.
- 6. THE CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL OR AS REQUIRED BY THE GENERAL PERMIT.
- 7. CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE PARKING AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES.
- 8. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISP()SED.
- 9. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL ON SITE. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- 11. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
- 12. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THE PLAN, SHALL BE INITIATED AS SOON AS PRACTICABLE.

ALL MEASURES STATED ON THE EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A 0.5" RAINFALL EVENT, AND CLEANED AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:

1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR DETERIORATION. 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED. WATERED AND RESEEDED AS NEEDED. FOR MAINTENANCE REQUIREMENTS REFER TO SECTION 981 OF THE OF THE FLORIDA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (LATEST EDITION).

3. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE.

4. THE CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCES AS CONDITIONS DEMAND. 5. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.

6. OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 55 CUBIC YARDS / ACRE.

ACTIVITIES:

EROSION CONTROL NOTES (CONT.)

13. STABILIZATION PRACTICES SHOULD BE INITIATED AS SOON AS PRACTICAL, BUT IN NO CASE MORE THAN 7 DAYS WHERE CONSTRUCTION HAS TEMPORARILY CEASED.

14. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 7 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRED IN THESE AREAS. REFER TO SECTION 981 OF THE STANDARD SPECIFICATIONS FOR SEEDING AND MAINTENANCE REQUIREMENTS.

15. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.

16. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED AS SOON AS POSSIBLE.

17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS IN CONJUNCTION WITH THE STABILIZATION OF THE SITE.

18. ON-SITE & OFF SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE EROSION CONTROL PLAN AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.

19. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.

20. DUE TO GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, ETC.) TO PREVENT EROSION.

21. ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY. THIS INCLUDES BACK FILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.

MAINTENANCE

7. ALL MAINTENANCE OPERATIONS SHALL BE DONE IN A TIMELY MANNER BUT IN NO CASE LATER THAN 2 CALENDAR DAYS FOLLOWING THE INSPECTION.

TYPICAL ENGINEER OBSERVATIONS

CONTRACTOR SHALL NOTIFY ENGINEER 48 HOURS IN ADVANCE OF THE FOLLOWING

- PRE-CONSTRUCTION MEETING
- SUBGRADE PREPARATION - BASE INSTALLATION
- ASPHALT INSTALLATION
- UNDERGROUND PIPING AND UTILTIES INSTALLATION - INSTALLATION OF STRUCTURES, DDCV, HYDRANTS, METERS, ETC.
- SIDEWALK INSTALLATION
- CONNECTIONS TO WATER AND SEWER MAINS - TESTS OF UTILITIES

3RD PARTY TEST REPORTS REQ'D


TEST REPORTS REQUIRED FOR CLOSE OUT INCLUDE, BUT ARE NOT LIMITED TO:

- DENSITY TEST REPORTS


- BACTERIOLOGICAL TESTS OF WATER SYSTEM - PRESSURE TEST OF WATER/SEWER - LEAK TESTS ON SEWER SYSTEM AND GREASE TRAPS - ANY OTHER TESTING REQUIRED BY THE AGENCY

> Always call 811 two full business days before you dig to have underground utilities located and marked.


LCOM



C-100



· · · · · · · · · · · · · · · · · · ·		: 		
				BY
				DATE
	EXISTING ASPHALT AND/OR CONCRETE PAVEMENT ONLY TO BE REMOVED OR 0 20 40 80			
87.87	PAVEMENT ONLY TO BE REMOVED OR RESTORED (REFER TO PAVEMENT DELINEATION PLAN)			S
	EXISTING LANDSCAPE AREA TO BE			REVISIONS
	EXISTING ASPHALT PAVING AND BASE TO			REV
	EXISTING CONCRETE PAVEMENT/SIDEWALK TO BE REMOVED			
FR				No.
			INC. -1 32960 -9689	
			ES, IN 4, FL 32-96	00000696
· · · · · · · · · · · · · · · · · · ·	PARCEL AND SEAL COAT (2 COATS) □ AND RESTRIPE (2 COATS) PER THE ✓		DCIATES BEACH, 72-562	0000
	TION COMMENCEMENT CITY REQUIREMENTS. THIS INCLUDES NTROL TO BE IN PLACE PARKING STALL STRIPES, PAVEMENT		ASSC ERO E	CA
	MARKINGS, STOP BARS, ETC.		AND 000, V	COM COM
			HORN - 798	LUKN.
	THESE DEMOLITION PLANS ARE BASED ON AVAILABLE UTILITY INFORMATION AND MAY OR MAY NOT BE ALL NCLUSIVE FOR THIS SITE. ANY UTILITIES ENCOUNTERED DURING DEMOLITION THAT ARE NOT DEPICTED/ADDRESSED ON THIS DRAWING SHOULD BE BROUGHT TO THE ATTENTION OF THE PROJECT	J	ALEY- 1, SU 562	LE Y
	ENGINEER IMMEDIATELY.	C	21 KIN STREE 772	W.KIM
3.			© 202 21st 3 PHONE:	M A
. 1	CONTRACTOR SHALL LIMIT ALL DEMOLITION ACTIVITIES TO THOSE AREAS DELINEATED ON THE CONSTRUCTION DRAWINGS UNLESS OTHERWISE DIRECTED BY THE DEVELOPER OR AS REQUIRED FOR		601 s	
	CONSTRUCTION OF IMPROVEMENTS.		2/3/2022	
1	CONTRACTOR TO USE CARE IN HANDLING DEBRIS FROM THE SITE TO ENSURE THE SAFETY OF THE PUBLIC. $\stackrel{=}{\vdash}$ HAUL ROUTE TO BE CLOSELY MONITORED FOR DEBRIS OR MATERIALS TRACKED ONTO ADJOINING ROADWAYS. SIDEWALKS, ETC. ROADWAYS AND WALKWAYS TO BE CLEARED DAILY OR AS NECESSARY TO MAINTAIN PUBLIC	LITTIN N	G * HEAR	
· · · · · · · · · · · · · · · · · · ·	SAFETY. STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH	M	8 - H 4	
i	MPLEMENTATION OF BEST MANAGEMENT PRACTICES. ON SITE STOCKPILE AND BORROW AREA LOCATIONS TO BE CETERMINED BY THE CONTRACTOR BASED CONSTRUCTION PHASING NEEDS AND SHALL BE LOCATED AND MAINTAINED AN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.	LICENS	STATE C	ONAL
	FOR ANY MATERIALS TO BE RECYCLED, CONTRACTOR MUST FIRST REMOVE ALL HAZARDOUS MATERIAL FROM THE MATERIALS TO BE RECYCLED IN ACCORDANCE WITH FEDERAL, STATE, AND LOCAL HAZARDOUS MATERIALS HANDLING AND DISPOSAL CRITERIA AND IN ACCORDANCE WITH ENVIRONMENTAL RECOMMENDATIONS PROVIDED BY THE PROJECT ENVIRONMENTAL CONSULTANT.		9 + PROFE	100/1
	RECYCLED MATERIALS TO BE USED AS REPLACEMENT MATERIAL WILL MEET APPLICABLE FDOT SPECIFICATIONS FOR \int_{Ω}^{\Box} THE MATERIAL BEING REPLACED. CONTRACTOR TO OBTAIN APPROVAL FROM THE ENGINEER OF RECORD FOR THE USE \Box OF ANY RECYCLED MATERIAL AS REPLACEMENT MATERIAL.	01 01	DTW NNN SDS	PVR
	THE CONTRACTOR IS RESPONSIBLE FOR THE DEMOLITION, REMOVAL, AND DISPOSAL (IN A LOCATION O APPROVED BY ALL GOVERNING AUTHORITIES) ALL STRUCTURES, PADS, WALLS, FLUMES, FOUNDATIONS,	ROJE		В≺
	PARKING, DRIVES, DRAINAGE, STRUCTURES, UTILITIES, ETC., SUCH THAT THE IMPROVEMENTS SHOWN ON THE REMAINING PLANS CAN BE CONSTRUCTED. ALL FACILITIES TO BE REMOVED SHALL BE UNDERCUT TO SUITABLE MATERIAL AND BROUGHT TO GRADE WITH SUITABLE COMPACTED FILL MATERIAL PER THE SPECIFICATIONS.		UZ/U SCALE A: DESIGNED E	
10.	THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL DEBRIS FROM THE SITE AND DISPOSING THE DEBRIS IN A LAWFUL MANNER. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS REQUIRED FOR		UZ SCALE DESIGN	
11.	DEMOLITION AND DISPOSAL.		Ľ	
	CONCERNING PORTIONS OF WORK WHICH MAY BE PERFORMED BY THE UTILITY COMPANY'S FORCES AND Z ANY FEES WHICH ARE TO BE PAID TO THE UTILITY COMPANY FOR THEIR SERVICES. THE CONTRACTOR IS		0 C	
12.	RESPONSIBLE FOR PAYING ALL FEES AND CHARGES.	A		
13.	EXISTING BUILDINGS PRIOR TO DEMOLITION OF THE BUILDINGS.	Ζ	Z	
	ASSUMES NO RESPONSIBILITY FOR THEIR ACCURACY. PRIOR TO THE START OF ANY DEMOLITION ACTIVITY, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES FOR ONSITE LOCATIONS OF EXISTING UTILITIES.	<u>0</u>		
	ALL EXISTING SEWERS, PIPING AND UTILITIES SHOWN ARE NOT TO BE INTERPRETED AS THE EXACT] [
	PROCEEDING WITH THE WORK. UTILITIES DETERMINED TO BE ABANDONED AND LEFT IN PLACE SHALL BE	エ	δ ^α	•
15.	ELECTRICAL, TELEPHONE, CABLE, WATER, FIBER OPTIC CABLE AND/OR GAS LINES NEEDING TO BE REMOVED \Box .	N N	<u>S</u>	
	OR RELOCATED SHALL BE COORDINATED WITH THE AFFECTED UTILITY COMPANY. ADEQUATE TIME SHALL BE \neg PROVIDED FOR RELOCATION AND CLOSE COORDINATION WITH THE UTILITY COMPANY IS NECESSARY TO \Box PROVIDE A SMOOTH TRANSITION IN UTILITY SERVICE. CONTRACTOR SHALL PAY CLOSE ATTENTION TO		Ö	
16.	EXISTING UTILITIES WITHIN THE ANY ROAD RIGHT OF WAY DURING CONSTRUCTION.	Ω	Ř	
	(AND OTHER APPROPRIATE BEST MANAGEMENT PRACTICES) AS APPROVED BY CONSTRUCTION MANAGER.			
 	DEMOLITION OF THE EXISTING FACILITIES.			AC
19.				-ORID.
	UTILITY DEPARTMENT TO PLAN PROPOSED IMPROVEMENTS AND TO ENSURE ADEQUATE FIRE PROTECTION IS CONSTANTLY AVAILABLE TO THE STORE AND SITE THROUGHOUT THIS SPECIFIC WORK AND THROUGH ALL PHASES OF CONSTRUCTION. CONTRACTOR WILL BE RESPONSIBLE FOR ARRANGING/PROVIDING ANY	Z		
	REQUIRED WATER MAIN SHUT OFFS WITH THE CITY/COUNTY DURING CONSTRUCTION. ANY COSTS ASSOCIATED WITH WATER MAIN SHUT OFFS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND NO EXTRA COMPENSATION WILL BE PROVIDED.	A A		
20.	T DAMAGE TO ALL EXISTING CONDITIONS TO REMAIN WILL BE REPLACED AT CONTRACTOR'S EXPENSE. $\downarrow \downarrow$	ם	S, L S, L	
	THE INTENT OF THE DEMOLITION PLAN IS TO DEPICT EXISTING FEATURES THAT ENCUMBER THE PROPOSED			
	INADVERTENTLY OMITTED FROM THE PLAN. THE CONTRACTOR IS REQUIRED TO THOROUGHLY INSPECT THE $\vdash \bigcirc$ SITE AS WELL AS REVIEW THE PLANS AND SPECIFICATIONS PRIOR TO SUBMITTING PRICING. CONTRACTOR WILL NOT RECEIVE ADDITIONAL COMPENSATION FOR INCIDENTAL ITEMS NOT SHOWN ON THIS DEMOLITION DI AN	Ŭ	ы По Ш	
22.	PLAN. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING AIRBORNE DUST AND POLLUTANTS BY USING WATER SPRINKLING OR OTHER SUITABLE MEANS OF CONTROL	Ž	PREPARED AMINGO S VESTMEN	NOL
23.	SPRINKLING OR OTHER SUITABLE MEANS OF CONTROL. PAVEMENT STRIPING AND MARKING MAY CONTAIN TRACE AMOUNTS OF LEAD, THE DISPOSAL OF ALL	AMIN	AM VE	ANTATION
	SUSPECTED LEAD-CONTAINING PAINT SHALL BE PERFORMED IN ACCORDANCE WITH 40 CODE OF FEDERAL REGULATIONS (CFR) PART 263 - LAND DISPOSAL REGULATIONS.	Ā	Ц Ц Х	PLAN
	Always call 811 two full business days before you dig to			ЪЧ
	have underground utilities located and marked.			CITY
	Sunshime 811.com	SHE	ET NUMBER	
		C	-200	



UPON IMPLEMENTATION AND INSTALLATION OF THE FOLLOWING AREAS: TRAILER, PARKING, LAYDOWN, PORTA-POTTY, WHEEL WASH, CONCRETE WASHOUT, FUEL AND MATERIAL STORAGE CONTAINERS, SOLID WASTE CONTAINERS, ETC., IMMEDIATELY DENOTE THEM ON THE SITE MAPS AND NOTE ANY CHANGES IN

3. INSTALL AND STABILIZE ANY NECESSARY HYDRAULIC CONTROL STRUCTURES (DIKES, CHECK DAMS,

HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM INSPECTION AND CERTIFICATION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER

ONTRACTOR TO BE RESPONSIBLE FOR OBTAINING ALL DEWATERING PERMITS NECESSARY FOR

2. TEMPORARILY SEED, THROUGHOUT CONSTRUCTION, DISTURBED AREAS THAT WILL BE INACTIVE FOR T

4. INSTALL INLET PROTECTION AT ALL STORM DRAIN INLETS AS EACH INLET IS INSTALLED. PERMANENTLY STABILIZE AREAS TO BE VEGETATED AS THEY ARE BROUGHT TO FINAL GRADE.

6. INSTALL APPROPRIATE INLET PROTECTION DEVICES FOR PAVED AREAS AS WORK PROGRESSES. 7. COMPLETE GRADING AND INSTALLATION OF PERMANENT STABILIZATION OVER ALL AREAS. 9. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AFTER INSPECTION AND APPROVAL OF THE ENGINEER AND STABILIZE ANY AREA DISTURBED BY THE REMOVAL OF BMPS.

10. CONTINUE DAILY INSPECTION REPORTS UNTIL THE FINAL DAILY INSPECTION IS SIGNED OFF BY THE CONSTRUCTION MANAGER THAT THE SITE IS FULLY STABILIZED AND THE PERMIT MAY BE TERMINATED.

ALL MEASURES STATED ON THIS SITE MAP, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES AND PRACTICES WHETHER TEMPORARY OR PERMANENT, SHALL BE AT ALL TIMES THE RESPONSIBILITY OF THE CONTRACTOR/PRIMARY PERMITEE. THESE MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:

1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED.

3. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE. 4. THE CONSTRUCTION EXITS SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE

5. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING 6. OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL

CONDITIONS AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN

1. CONTRACTOR TO CONSIDER POTENTIAL DEWATERING ACTIVITIES WHEN PREPARING BID DOCUMENTS 2. CONTRACTOR SHALL OBTAIN ANY NECESSARY DEWATERING PERMITS AS SITE CONDITIONS AND

3. CONTRACTOR TO USE B.M.P.'S TO ENSURE COMPLIANCE WITH NPDES AND WATER MANAGEMENT DISTRICT REGULATIONS FOR STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES AND

4. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR, OR CONCURRENT WITH LAND DISTURBING

STONE SIZE - USE #2 STONE OR RECLAIMED RECYCLED CONCRETE EQUIVALENT.

WIDTH - TWENTY (20) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS


6. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, MOUNTABLE BERM WITH 5:1 SLOPES

OF FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC

WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAYS. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. USE WATERING TRUCK OR ONSITE SUPPLY AS 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN EVENT.

ING LAND CLEARING, SOIL TO BE JLCHED. ING SHALL COMMENCE UNTIL A OF THE REQUIRED EROSION RICADES HAS BEEN OBTAINED. AY BE OBTAINED SUBSEQUENT TO FION OF THE CONTROL HIS PERMIT SHALL BE POSTED IN ION SHOWN ELSEWHERE ON THIS ADES AND SILT FENCES WILL ONITORED FOR COMPLIANCE BY G THE PERMITTED DEVELOPMENT OF OCCUPANCY FOR THE	ACREAGE SUMMA	RY
	TOTAL PROJECT AREA (PHASE I)	7.68
	ON-SITE DISTURBED AREA	7.68
	OFF-SITE DISTURBED AREA	0.00
	TOTAL DISTURBED AREA	7.68
DNITORED FOR COMPLIANCE BY	IMPERVIOUS AREA AT COMPLETION	3.238
- ···-··	PERVIOUS / SEEDED AREA AT COMPLETION / POND AREA	3.238
D AND DISPOSED OF BY THE		

TATION CO	NTR	OL (OPER	ATIO	N TIN	NE S	SCHE	DULE				
R TO COMPL												
	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	0CT	NOV	DEC
XITS												
RES												
TURES												
NSTRUCTION												



RUMBLE PAD (SEE SHEET C-202)

SURFACE WATER FLOW DIRECTION PROPERTY LINE LIMITS OF DISTURBANCE

CONSTRUCTION FENCE _____X_____

140

 \bigotimes

 \sim

_____ID____

 \bigcirc Locald Links and the second in $\overline{\sim}$ C Summer of B Villenau 2/3/2022 Ο Ŷ Ш N N Ο 4 \mathbf{O} Ζ Ο S Οd R Ш TOR FOR Ś D O ROCERY MING Ž (n

Always call 811 two full business days before you dig to have underground utilities located and marked.

LCOM


SHEET NUMBER


C-201

Sunshine

EROSION CONTROL NOTES


- 1. SEDIMENT BASINS AND TRAPS, PERIMETER DIKES, SEDIMENT BARRIERS AND OTHER MEASURES INTENDED TO TRAP SEDIMENT SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND DISTURBING ACTIVITY AND SHALL BE MADE FUNCTIONAL BEFORE UP-SLOPE LAND DISTURBANCE TAKES PLACE.
- 2. ALL SEDIMENT CONTROL MEASURES ARE TO BE ADJUSTED TO MEET FIELD CONDITIONS AT THE TIME OF CONSTRUCTION AND BE CONSTRUCTED PRIOR TO ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL ON BALANCE OF SITE. PERIMETER SEDIMENT BARRIERS SHALL BE CONSTRUCTED TO PREVENT SEDIMENT OR TRASH FROM FLOWING OR FLOATING ON TO ADJACENT PROPERTIES.
- 3. PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE, TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN (7) DAYS TO DENUDED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN UNDISTURBED FOR LONGER THAN 30 DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT UNDISTURBED FOR MORE THAN ONE YEAR.
- 4. DURING CONSTRUCTION OF THE PROJECT, SOIL STOCK PILES SHALL BE STABILIZED, COVERED OR CONTAINED WITH SEDIMENT TRAPPING MEASURES. THE APPLICANT IS RESPONSIBLE FOR THE TEMPORARY PROTECTION AND PERMANENT STABILIZATION OF ALL SOIL STOCKPILES ON SITE AS WELL AS SOIL INTENTIONALLY TRANSPORTED FROM THE PROJECT SITE.
- 5. A PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED ON DENUDED AREAS NOT OTHERWISE PERMANENTLY STABILIZED.
- 6. AFTER ANY SIGNIFICANT RAINFALL, SEDIMENT CONTROL STRUCTURES WILL BE INSPECTED FOR INTEGRITY. ANY DAMAGED DEVICES SHALL BE CORRECTED IMMEDIATELY.
- 7. CONCENTRATED RUNOFF SHALL NOT FLOW DOWN CUT OR FILL SLOPES UNLESS CONTAINED WITHIN AN ADEQUATE TEMPORARY OR PERMANENT CHANNEL, FLUME, SLOPE DRAIN STRUCTURE OR APPROVED CONTROL.
- 8. SEDIMENT WILL BE PREVENTED FROM ENTERING ANY STORM WATER SYSTEM, DITCH OR CHANNEL. ALL STORM WATER INLETS THAT ARE MADE OPERABLE DURING CONSTRUCTION SHALL BE PROTECTED SO THAT SEDIMENT-LADEN WATER CANNOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT.
- 9. WHEN WORK IN A LIVE WATERCOURSE IS PERFORMED, PRECAUTIONS SHALL BE TAKEN TO MINIMIZE ENCROACHMENT, CONTROL SEDIMENT TRANSPORT AND STABILIZE THE WORK AREA TO THE GREATEST EXTENT POSSIBLE DURING CONSTRUCTION.
- 10. PERIODIC INSPECTION AND MAINTENANCE OF ALL SEDIMENT CONTROL STRUCTURES MUST BE PROVIDED TO ENSURE INTENDED PURPOSE IS ACCOMPLISHED. THE DEVELOPER, OWNER AND/OR CONTRACTOR SHALL BE CONTINUALLY RESPONSIBLE FOR ALL SEDIMENT CONTROLS. SEDIMENT CONTROL MEASURES SHALL BE IN WORKING CONDITION AT THE END OF EACH WORKING DAY.
- 11. WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED PUBLIC ROADS, PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT BY TRACKING ONTO THE PAVED SURFACE. WHERE SEDIMENT IS TRANSPORTED ONTO A PUBLIC ROAD SURFACE WITH CURBS AND GUTTERS, THE ROAD SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY. SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER. THIS PROVISION SHALL APPLY TO INDIVIDUAL SUBDIVISION LOTS AS WELL AS TO LARGER LAND DISTURBING ACTIVITIES.
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.
 PROPERTIES AND WATERWAYS DOWNSTREAM FROM CONSTRUCTION SITES SHALL BE PROTECTED FROM SEDIMENT DEPOSITION AND EROSION AT
- ALL TIMES DURING CONSTRUCTION.
- 14. CONTRACTOR IS RESPONSIBLE FOR ALL SURFACE WATER DISCHARGES, RAINFALL RUN OFF OR DEWATERING ACTIVITIES.
- 15. CONTRACTOR MUST INCORPORATE ALL BMP'S NECESSARY TO MEET OR EXCEED STATE WATER QUALITY AND SWPPP REQUIREMENTS.
- 16. THE POLLUTION PREVENTION PLAN IS A MINIMUM GUIDELINE ONLY, ADDITIONAL BMP'S MAY BE NECESSARY AT CONTRACTOR'S EXPENSE.







PROJECT NAME: FLAMINGO PLAZA LATITIDE: N 26°8'40" LONGITUDE: W 80°18'46" OWNER: FLAMINGO SUNRISE INVESTMENT LLC OWNER'S ADDRESS: 336 E. DANIA BEACH BLVD. DANIA, FL 33004 DESCRIPTION OR NATURE OF CONSTRUCTION ACTIVITY: CONSTRUCTION OF INFRASTRUCTURE FOR SHOPPING CENTER SOIL DISTURBING ACTIVITIES INCLUDE: CONSTRUCTION OF EROSION AND SEDIMENT CONTROLS, CLEARING AND GRUBBING, GRADING, AND CONSTRUCTION OF OF STORM SEWER. PROJECT AREA CONTAINS ±7.675 ACRES. SEQUENCE OF MAJOR ACTIVITIES: 1. REFER TO SHEET C300 SITE PLAN OVERALL NAME OF RECEIVING WATER; ONSITE LAKE THEN PLANTATION ACRES IMPROVEMENT DISTRICT CANAL C-58 CONTROLS EROSION AND SEDIMENTATION CONTROLS STABILIZATION PRACTICES TEMPORARY STABILIZATION: TOP OF SOIL STOCK PILES AND DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR AT LEAST 21 DAYS WILL BE STABILIZED WITH TEMPORARY GRASS AND MULCH NO LATER THAN 5 DAYS FROM THE LAST CONSTRUCTION ACTIVITY. GRASS SEED SHALL BE A MIXTURE OF 20 PARTS OF BERMUDA SEED AND 80 PARTS OF PENSACOLA BAHIA THE SEPARATE TYPES OF SEED SHALL BE BE THOROUGHLY DRY MIXED IMMEDIATELY BEFORE SOWING. SEED WHICH HAS BECOME WET SHALL NOT BE USED. THE MULCH MATERIAL USED SHALL NORMALLY BE DRY MULCH. DRY MULCH SHALL BE STRAW OR HAY, CONSISTING OF OAT, RYE OR WHEAT STRAW, OR OF PANGOLA, PEANUT, COASTAL BERMUDA OR BAHIA GRASS HAY. ONLY UNDETERIORATED MULCH WHICH CAN BE READILY CUT INTO THE SOIL SHALL BE USED. AREAS OF THE SITE WHICH ARE TO BE PAVED WILL BE TEMPORARILY STABILIZED BY APPLYING STABILIZATION AND BASE. PERMANENT STABILIZATION: DISTRUBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASES SHALL BE STABILIZED PER LANDSCAPE PLAN NO LATER THAN 5 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY. STRUCTURAL PRACTICES STAKED SILT FENCE: THE STAKED SILT FENCES WILL BE CONSTRUCTED PER PLAN. THESE DEVICES WILL STOP AND DIVERT RUNOFF TO THE SEDIMENT BASINS. STORMWATER MANAGMENT STORMWATER DRAINAGE WILL BE PROVIDED BY CURBING, STORM SEWER, WET PONDS, DRY PONDS AND CATCH BASIN SYSTEM FOR THE DEVELOPED AREAS. WHEN CONSTRUCTION IS COMPLETE THE IMPROVED PORTION OF THE SITE WILL BE TREATED WITH WITH AN EXISTING WATERBODY TO THE SOUTHEAST OF THE SUBJECT PROPERTY. OTHER CONTROLS WASTE DISPOSAL WASTE MATERIALS: ALL WASTE MATERIAL WILL BE COLLECTED AND STORED IN DUMPSTERS PER LOCAL AGENCIES REGULATIONS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTERS. THE DUMPSTERS WILL BE EMPTIED A MINIMUM OF ONCE A WEEK OR MORE OFTEN IF NECESSARY, AND THE TRASH WILL BE HAULED TO A REGISTERED LANDFILL OR DISPOSAL. NO CONSTRUCTION MATERIALS WILL BE BURIED ON-SITE. ALL PERSONNEL WILL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL. NOTICES STATING THESE PRACTICES WILL BE POSTED IN THE ON-SITE OFFICE TRAILER AND THE CONSTRUCTION MANAGER RESPONSIBLE FOR THE DAY-TO-DAY-SITE OPERATIONS, WILL BE RESPONSIBLE FOR SEEING THAT THESE PROCEDURES AND FOLLOWED. HAZARDOUS WASTE: ALL HAZARDOUS WASTE MATERIALS, IF ENCOUTERED, WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED. SANITARY WASTE: ALL SANITARY WASTE WILL BE COLLECTED FROM PORTABLE UNITS A MINIMUM OF THREE TIMES PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR, AS REQUIRED BY LOCAL REGULATION. OFFSITE VEHICLE TRACKING STABILIZED CONSTRUCTION ENTRANCES SHALL BE PROVIDED TO HELP REDUCE VEHICLE TRACKING OF SEDIMENTS. THE PAVED STREETS WILL BE CLEANED AS NEEDED TO REMOVED ANY EXCESS MUD, DIRT OR ROCK TRACKED FROM THE SITE. DUMP TRUCKS HAULING MATERIAL FROM OR TO THE SITE WILL BE COVERED WITH A TARPAULIN AT ALL TIMES.


TIMING OF CONTROL MEASURES	SPILL CONTROL PRACTICES	
AS INDICATED IN THE SEQUENCE OF MAJOR ACTIVITIES, STAKED SILT BARRIERS, STABILIZED CONSTRUCTION ENTRANCES AND SEDIMENT BASINS WILL BE CONSTRUCTED PRIOR TO CLEARING OR GRADING OF ANY OTHER PORTIONS OF THE SITE. AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN 21 DAYS WILL BE STABILIZED WITH A TEMPORARY GRASS AND MULCH WITHIN 5 DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN THAT AREA, THAT AREA WILL BE STABILIZED WITH PERMANENT SOD. AFTER THE ENTIRE SITE IS STABILIZED, THE ACCUMULATED SEDIMENT WILL BE REMOVED FROM THE TRAPS AND THE STAKED SILT BARRIERS WILL BE REMOVED.	IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP: MANUFACTURERS' RECOMMEND METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ON-SITE. EQUIPMENT AND MATERIALS WILL INCLUDE, BUT NOT BE LIMITED TO, BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND,	ON ANY ELECTR
CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE AND LOCAL REGULATIONS	SAWDUST AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY. THE SPILL AREAS WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.	VERIFIED
THE STORM WATER POLLUTION PREVENTION PLAN REFLECTS THE SOUTH FLORIDA WATER MANAGEMENT DISTRICTS (SFWMD) REQUIREMENTS FOR STORM WATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL, AS ESTABLISHED BY THE FLORIDA ADMINISTRATIVE CODE, CHAPTER 40D-4 AND 40D-40. TO ENSURE COMPLIANCE, THIS PLAN WAS PREPARED IN ACCORDANCE WITH SFWMD'S "BASIS OF REVIEW FOR SURFACE WATER MANAGEMENT PERMIT APPLICATIONS WITHIN THE SOUTH WEST FLORIDA WATER MANAGEMENT DISTRICT. 'THIS PLAN ALSO REFLECTS THE REQUIREMENTS OF THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION.	SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEAN UP MEASURES WILL ALSO BE INCLUDED.	URE MUST BE
MAINTENANCE INSPECTION PROCEDURES	THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS, WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. HE WILL DESIGNATE OTHER SITE PERSONNEL WHO WILL RECEIVE SPILL PREVENTION AND CLEAN UP TRAINING. THESE INDIVIDUALS WILL EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE NAMES OF RESPONSIBLE SPILL PERSONNEL WILL BE POSTED IN THE MATERIAL STORAGE AREA AND IN THE OFFICE TRAILER ON-SITE.	SIGNATI
EROSION AND SEDIMENT CONTROL INSPECTION AND MAINTENANCE PRACTICES		DIGITAL
THESE ARE THE INSPECTION AND MAINTENANCE PRACTICES THAT SHALL BE USED TO MAINTAIN EROSION AND SEDIMENT CONTROL. ALL CONTROL MEASURES IN DISTURBED AREAS WILL BE INSPECTED AT LEAST ONCE EACH WEEK AND WITHIN 24 HOURS OF THE END OF ANY STORM EVENT OF 0.25 INCHES OR GREATER BY A CONTRACTORS REPRESENTATIVE. (WHERE SITES HAVE BEEN FINALLY STABILIZED SUCH INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE FOR MONTH). ALL MEASURES WHERE SITES HAVE BEEN FINALLY STABIL	NOTICE OF INTENT (NOI) / NOTICE OF TERMINATION (NOT)	D THE
ANT STOKE EVENT OF 0.25 INCHES OR GREATER BY A CONTRACTORS REPRESENTATIVE. (WHERE SITES HAVE BEEN FINALLY STABILIZED SUCH INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH.) ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER; IF A REPAIR IS NECESSARY IT WILL BE INITIATED WITHIN 24 HOURS OF REPORT. BUILT UP SEDIMENT WILL BE REMOVED FROM SILT FENCE WHEN IT HAS BEEN REACHED ONE-THIRD THE HEIGHT OF THE FENCE. SILT FENCE WILL BE INSPECTED REGULARLY FOR DEPTH OF SEDIMENT, TEARS, TO SEE IF THE FABRIC IS SECURELY ATTACHED TO THE FENCE POSTS, AND TO SEE THAT THE FENCE POSTS ARE FIRMLY IN THE GROUND. THE SEDIMENT BASINS WILL BE THE INSPECTED FOR DEPTH OF SEDIMENT, AND BUILT UP SEDIMENT WILL BE REMOVED WHEN IT REACHES 10 PERCENT OF THE DESIGN CAPACITY OR AT THE END OF THE JOB. TEMPORARY AND PERMANENT GRASSING, MULCHING AND SODDING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND HEALTHY GROWTH. A MAINTENANCE INSPECTION REPORT SHALL BE MADE AFTER EACH INSPECTION BY THE CONTRACTOR AND SHALL BE KEPT IN A ACTIVE LOG READILY AVAILABLE AT THE JOB SITE CONSTRUCTION TRAILER. THE SITE SUPERINTENDENT WILL SELECT INDIVIDUALS WH-M WILL BE RESPONSIBLE FOR MAINTENANCE AND REPAR ACTIVITIES. FILLING OUT THE INSPECTION AND MAINTENANCE REPORT WILL BE BY THE CONTRACTOR. PERSONNEL SELECTED FOR MAINTENANCE RESPONSIBILITIES WILL RECEIVE TRAINING FROM THE SITE SUPERINTENDENT. THEY WILL BE TRAINED IN ALL MAINTENANCE PRACTICES NECESSARY FOR KEEPING THE EROSION AND SEDIMENT CONTROLS USED ON-SITE IN GOOD WORKING ORDER.	 THIS NOTICE OF INTENT (NOI) FORM IS TO BE COMPLETED AND SUBMITTED TO THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP) BEFORE USE OF THE GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES PROVIDED IN SUBSECTION 62-621.300(4), F.A.C. A NOTICE OF TERMINATION WILL BE SUBMITTED TO EPA AFTER THE CONSTRUCTION HAS BEEN COMPLETED AND THE SITE HAS UNDERGONE FINAL STABILIZATION. POLLUTION PREVENTION PLAN CERTIFICATION 	SIGNED AND SEALED A SIGNED AND SEALED A SIGNED AND SEALED A SIGNED AND SEALED A ASSOCIATES, INC. VERO BEACH, FL 3296 AX: 772-562-9689 CA 00000696
		FRED SI 300, VI 301, FA
T IS EXPECTED THAT THE FOLLOWING NON-STORM WATER DISCHARGES WILL OCCUR FROM THE SITE DURING THE CONSTRUCTION PERIOD: WATER FROM FIRE FIGHTING ACTIVITIES, FIRE HYDRANT FLUSHING, WATER LINE FLUSHING, WATER USED TO SPRAY OFF LOOSE SOILS FROM PEHICLES, DUST CONTFOL, PAVEMENT WASH WATERS (WHERE NO SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE OCCURRED). ALL NON-STORM WATER DISCHARGES WILL BE DIRECTED TO THE SEDIMENT BASIN PRIOR TO DISCHARGE. SROUNDWATER DEWATERING ACTIVITIES ARE NOT COVERED BY THIS PERMIT. THE CONTRACTOR MUST APPLY FOR COVERAGE UNDER THE DENERIC PERMIT FOR THE DISCHARGE OF PRODUCED GROUNDWATER FROM ANY NON-CONTAMINATED SITE ACTIVITY PURSUANT TO 32-621.300(2), F.A.C.	I CERTIFY UNDER PENALTY OF LAW THAT THESE CONSTRUCTION PLANS, THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM, AS SHOWN ON THESE CONSTRUCTION PLANS, DESIGNED TO ASSURE THAT APPROPRIATE POLLUTION PREVENTION MEASURES ARE IMPLEMENTED DURING CONSTRUCTION AND TO ASSURE THAT THE QUALIFED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION. THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF TRUE, ACCURATE AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.	MENT ARE NOT CONSIG
INVENTORY FOR POLLUTION PREVENTION PLAN	OWNER:	2/3/2022
HE MATERIALS OR SUBSTANCES LISTED BELOW ARE EXPECTED, BUT NOT LIMITED, TO BE PRESENT ON-SITE DURING CONSTRUCTION:	SIGNED:	
CONCRETE DETERGENTS PAINTS (ENAMEL AND LATEX) METAL STUDS GLASS TAR	NAME AND TITLE:	TED COPIES
SAND FERTILIZERS PETROLEUM BASE() PRODUCTS AND FUELS CLEANING SOLVENTS WOOD	ADDRESS:	
MASONRY BLOCK ROOFING SHINGLES STONE	NAME AND TITLE:	RS RS CT THE SEA
SPILL PREVENTION		NT T0 PR0JE 721900 DATE /03/2 AS SH AS SH BY
MATERIAL MANAGEMENT PRACTICES		ADJACEN KHA F 1472 02/(02/(02/(DESIGNED DRAWN B
HE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER CCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES TO STORM WATER RUNOFF. OOD HOUSEKEEPING:		DL DIL
HE FOLLOWING GOOD HOUSEKEEPING PRACTICES SHALL BE FOLLOWED ON-SITE DURING THE CONSTRUCTION PROJECT. N EFFORT SHALL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO DO THE JOB ALL MATERIALS STORED ON-SITE SHALL BE TORED NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER CONTAINED NCLOSURE, PRODUCTS SHALL BE KEPT IN THEIR ORIGINAL MANUFACTURER'S LABELED CONTAINERS. SUBSTANCES SHALL NOT BE MIXED ITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER. WHENEVER POSSIBLE, ALL OF A PRODUCT SHALL BE USED UP EFORE DISPOSING OF THE CONTAINER. MANUFACTURERS' RECOMMENDATIONS FOR PROPER USE AND DISPOSAL SHALL BE FOLLOWED. THE ITE SUPERINTENDENT SHALL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ON-SITE.	CONTRACTOR'S CERTIFICATION	DETA
AZARDOUS PRODUCTS: HESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS. RODUCTS SHALL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE ORIGINAL LABELS AND MATERIAL SAFETY ATA SHALL BE RETAINED; THEY CONTAIN IMPORTANT PRODUCT INFORMATION. IF SURPLUS PRODUCT MUST BE DISPOSED OF, ANUFACTURERS' OR LOCAL AND STATE RECOMMENDED METHODS OF PROPER DISPOSAL SHALL BE FOLLOWED. HE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ON-SITE: ETROLEUM PRODUCTS:	I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERIC STORM WATER PERMIT ISSUED PURSUANT TO SECTION 403.0085, F.S., THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATE WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION. SIGNATURE FOR RESPONSIBLE FOR	ANDLO
LL ON-SITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF AKAGE, PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT JBSTANCES USED ON-SITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.	COMPANY: COMPANY:	ES BY
ERTILIZERS: ERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER. ONCE APPLIED, FERTILIZER ILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER. STORAGE WILL BE IN A COVERED SHED. THE CONTENTS OF ANY ARTICALLY USED BAG OF FERTILIZER WILL BE TRANSFERRED TO BE SEALABLE PLASTIC BIN TO AVOID SPILLS.	NAME: NAME: TITLE: TITLE:	OT OT SE
AINTS: LL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE TORM SEWER SYSTEM BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURERS' INSTRUCTIONS OR STATE AND LOCAL EGULATIONS.	DATE: DATE: COMPANY: COMPANY:	Ш Signed
DNCRETE TRUCKS:	NAME: NAME:	IGITALLY
ONTRACTOR SHALL DESIGNATE AN AREA FOR DISCHARGE OF SURPLUS CONCRETE OR DRUM WASH WATER AND SHALL INSTALL A ONTAINMENT BERM AROUND THIS AREA TO PREVENT RUNOFF TO THE REMAINDER OF THE SITE. HARD DEBRIS SHALL BE DISPOSED OF BY ONTRACTOR UPON COMPLETION OF THE PROJECT.	TITLE: TITLE: DATE: DATE:	
	COMPANY: COMPANY:	R R ARIS , LL(
	NAME: NAME: TITLE: TITLE:	D FOI NTS
	DATE: DATE:	GO MEI
		AIN MIN TEST
	Always call 811 two full business days before you di	
,我们就是你们的,你们就是你们的,你们就是你们的,你们就是你们的,你们就是你们的你们,你们就是你们的你,你们就是你们的。""你们,你们们不是你们的,你们们不是你们	have underground utilities located and marked.	• • • • • • • • • • • • • • • • • • •




(A) PROPOSED CURB				
				B
B PROPOSED LIGHT POLE			NORTH	ATE
C EXISTING LIGHT POLE			NORTH	DA
(D) ELECTRIC CAR CHARGIN	G STATION		EI ANY	
(F) STOP BAR			HIC SCALE IN FEET $_{Z}$	
G MAIN BUILDING ENTRAN	CE (CUSTOMERS)			
H PROPOSED CURB & GU	TER		VERIFIED	S S S S S S S S S S S S S S S S S S S
	3LIC ACCESS)	LEGEND	L B	SIONS
(J) MOVABLE TEMPORARY (WITH 5' CLEAR ON ALL S	GENERATOR LOCATION (8'X5' X 22.5' AREA) IDES.			REVI
K ADA ACCESSIBLE PARKI	NG SPACES	(#) 1	NUMBER OF PARKING SPACES	
L 48" MINIMUM WIDTH ACC EMERGENCY EGRESS, A	ESSIBLE ROUTE CONNECTION FRONT DOOR, ND ACCESSIBLE PARKING TO PUBLIC RIGHT OF	WAY CC 0	CART CORRAL (5 TOTAL)	
M TRUCK LOADING DOCK.	ADD 6" STRIPING TO DELINEATE LANES	F	PROPOSED CURB	
\bigcirc	PAINTING YELLOW FOR GAS METER	E	EXISTING CURB	
			EXISTING LIGHT POLE	
 (P) EXTERIOR CART CORRA (Q) SEPARATE DUMPSTER F 	L OR TRASH, RECYCLE, AND COMPOST.		PROPOSED LIGHT POLE	ç o
\bigcirc	REL ON 8'X5' CONCRETE PAD		ADA PATH	INC. 9689
S TRANSFORMER		× E	ຊ EASEMENT (SEE SURVEY)	
T TRASH BINS			D N V	000066
-				
SITE DATA PROJECT DESCRIPTION:	MODIFICATION OF BUILDING PARKING			
	LOT AND OTHER IMPROVEMENTS	ARE COMPLETE T SHALL SANDBLAS		
LOCATION:	WEST SUNRISE BOULEVARD AND FLAMINGO ROAD	STRIPING EXCEPT	FOR THE JAREDS	
ADDRESS:	12300 WEST SUNRISE BOUELEVARD PLANTATION, FLORIDA 33323 BROWARD COUNTY	AND RESTRIPE (2	COATS) PER THE	KIMLEY KIMLEY 772-56 KIMLEY-
ZONING DISTRICT:	BROWARD COUNTY B-2L (LIMITED COMMUNITY BUSINESS)	PARKING STALL S		
LAND USE:	COMMERCIAL	MARKINGS, STOP		21s
FLOOD ZONE:	FLOOD ZONE: AH; BASE FLOOD ELEVATION: 6 FEET; PANEL #: 12011C030H		DOCUMENT	601
	& 12011C0345H; COMMUNITY #: 120054; MAP DATE: 08/18/2014			3/14/2022
LAND USE SUMMARY (FOLIO: 494 BUILDING AREA:	036480020, 494036480040, & 49403648 0010):		THIS N	NUNITE X SAL
QUARTERDECK GROCERY	7,000 SF 44,251 SF		O E E	NONG * 833NO
JARED'S TOTAL	6,134 SF 57,392 SF 1.318 AC 17.17%		COPIES	No. 63166
OPENSPACE AREA:	135,875 SF 3.119 AC 40.64%		ITED	No. 6316 STATE OF STATE OF STATE OF CORIDPAL
IMPERVIOUS AREA (PAVEMENT): TOTAL SITE AREA:	141,066 SF 3.238 42.19% 334,333 SF 7.68 AC (100%)		PRINTED	
BUILDING SETBACK:	REQUIRED PROVIDED		SEAL.	
FRONT (SUNRISE) REAR SIDE (EAST)	37.5' 324.90' 37.5' 37.70' 37.5' 289.00'		LE THE	JECT 001 SHOWN DTW SDS PVR
SIDE (WEST) (NOTE ALL DISTANCES ARE FROM	37.5' 82.10' M THE PROPERTY LINE.)		0 1 1	
			ADJACENT	
				KH, 14 SCALE SCALE DESIGN DESIGN DRAWN
			DATE	
PARKING CALCULATIO 1. GROCERY 2. JARED'S JEWLER	44,251 S.F. / 200 S.F. PER SPACE =		THE T	
 SUNTRUST BANK QUARTERDECK 		= 11 SPACES = 50 SPACES	о N	
TOTAL REQUIRED		304 SPACES		Z
PARKING SUMMARY: STANDARD	REQUIRED PROVIDED 292 262		WILFONG	AN
ACCESSIBLE TOTAL	<u>12</u> <u>12</u> 304 274		D. WII	
AN ADMINISTRATIVE	PARKING WAIVER FOR PARKING WILL BE REQU	IRED SINCE 10% UNDER COD	אר (9.9%). ער פון (9.9%). ער פון	
			× B	
			ALED	N N
			ND SEALED	S S
			U N N	S S
 34.0'-	F.F.E. 7.53'		SIGNED AND	S
 34.0'-	53.0' PROPOSED TRENCH DRAIN		SIGNED AND	
34.0'-	53.0'	~_ E	U N N	LORIDA
34.0'-	53.0' PROPOSED TRENCH DRAIN	~_ E	CXISTING LOADING DOCKS (TO REMAIN)	FLORIDA
34.0'-	53.0' PROPOSED TRENCH DRAIN		CXISTING LOADING DOCKS (TO REMAIN)	LORIDA
34.0'-	53.0' PROPOSED TRENCH DRAIN		CXISTING LOADING DOCKS (TO REMAIN)	TORE RISE LLC FLORIDA
	53.0' PROPOSED TRENCH DRAIN		EXISTING LOADING DOCKS (TO REMAIN) F.F.E. 7.53'	STORE FOR UNRISE TS, LLC FLORIDA
EXISTING WALL TO BE REMOVED	53.0' PROPOSED TRENCH DRAIN		EXISTING LOADING DOCKS (TO REMAIN)	Y STORE ED FOR SUNRISE ENTS, LLC FLORIDA
	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A A A A A A A A A A A A A		EXISTING LOADING DOCKS (TO REMAIN) F.F.E. 7.53'	Y STORE ED FOR SUNRISE ENTS, LLC FLORIDA
EXISTING WALL TO BE REMOVED PROPOSED SCREE	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A A A A A A A A A A A A A	SIDEWALK WITH WITH 18" CURB	EXISTING LOADING DOCKS (TO REMAIN) F.F.E. 7.53'	Y STORE ED FOR SUNRISE ENTS, LLC FLORIDA
EXISTING WALL TO BE REMOVED PROPOSED SCREE	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A DOCK 2 A DOCK 2 A A A A A A A A A A A A A A A		EXISTING LOADING DOCKS (TO REMAIN) F.F.E. 7.53'	OCERY STORE PREPARED FOR AMINGO SUNRISE JVESTMENTS, LLC
EXISTING WALL TO BE REMOVED PROPOSED SCREE	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A A A A A A A A A A A A A	SIDEWALK WITH WITH 18" CURB	EXISTING LOADING DOCKS (TO REMAIN) F.F.E. 7.53'	OCERY STORE PREPARED FOR AMINGO SUNRISE JVESTMENTS, LLC
EXISTING WALL TO BE REMOVED PROPOSED SCREE	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A DOCK 2 A DOCK 2 A RAISED HANDRAIL - RAISED HANDRAIL TRANSITION DETAIL A	SIDEWALK WITH WITH 18" CURB DNING TO FLUSH	TRUE TRUE TRUE TRUE TRUE TRUE TRUE TRUE	ROCERY STORE PREPARED FOR FLAMINGO SUNRISE INVESTMENTS, LLC LANTATION FLORIDA
EXISTING WALL TO BE REMOVED PROPOSED SCREE	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A DOCK 2 A DOCK 2 A RAISED HANDRAIL - RAISED HANDRAIL TRANSITIC DETAIL A	SIDEWALK WITH WITH 18" CURB DNING TO FLUSH	EXISTING LOADING DOCKS (TO REMAIN) F.F.E. 7.53'	GROCERY STORE <pre>PREPARED FOR PREPARED FOR FLAMINGO SUNRISE INVESTMENTS, LLC OITY OF PLANTATION </pre>
EXISTING WALL TO BE REMOVED PROPOSED SCREE	53.0' PROPOSED TRENCH DRAIN GRATE: 4.96' A DOCK 1 A DOCK 2 A DOCK 2 A RAISED HANDRAIL - RAISED HANDRAIL TRANSITIC DETAIL A	SIDEWALK WITH WITH 18" CURB DNING TO FLUSH	TRUE TRUE TRUE TRUE TRUE TRUE TRUE TRUE	GROCERY STORE <pre>PREPARED FOR PREPARED FOR FLAMINGO SUNRISE INVESTMENTS, LLC TY OF PLANTATION TY OF PLAN</pre>







GRAPHIC SCALE IN FEET 0 20 40 8



STANDARD DUTY ASPHALT (SEE SHEET C-401)

HEAVY DUTY ASPHALT (SEE SHEET C-401)

HEAVY DUTY CONCRETE (SEE SHEET C-401)

TRUCK LOADING PAD (SEE ARCHITECTURAL/STRUCTURAL PLANS)

SIDEWALK (SEE SHEET C-401)

> ONCE THE PROJECT IMPROVEMENTS ARE COMPLETE THE CONTRACTOR SHALL SANDBLAST ALL EXISTING STRIPING EXCEPT FOR THE JAREDS PARCEL AND SEAL COAT (2 COATS) AND RESTRIPE (2 COATS) PER THE CITY REQUIREMENTS. THIS INCLUDES PARKING STALL STRIPES, PAVEMENT MARKINGS, STOP BARS, ETC.

		КНА PROJECT 147219001	ALL DAY D. WITH			
	DAVEMENT	DATE 02/03/22	CONCENSE NOT			
EI AMINGO SI INDISE		SCALE AS SHOWN		a 2021 kimi fy-horn and Associates Inc.		
	DELINEATION PLAN	DESIGNED BY GDW	DI STATE OF CONTROL	~~~~~		
INVESTMENTS, LLC		DRAWN BY RS	LAC FLORIDA CON	PHONE: //Z-36Z-/981 FAX: //Z-36Z-9069 WWW.KIMLEY-HORN.COM CA 0000696		
FI ORIDA		CHECKED BY GDW	VINONAL EVIN		No. REVISIONS	DATE BY

Always call 811 two full business days before you dig to have underground utilities located and marked. Sunshine of comparison

SHEET NUMBER

C-402

PLANTATION ACRES IMPROVEMENT DISTRICT PERMIT

PROJECT TITLE: <u>FLAMINGO PL/</u> STREET ADDRESS: <u>12300 W. SU</u>	JNRISE BOULEVARD, PLA	NTATION. FL. 33323		
OCATION: Tract(s)	1/4 Section	n 36	Township 49	Range 40 E
Plat Book	Page	36	Block	Lot
URPOSE COMMERCIAL			(residential,	agricultural, commercial, etc.)
ROJECT SIZE: This phase: 7.6	38 acres	Total: 7.68 acr		
ESCRIPTION OF WORK TO BE	PERMITTED NEW GROC	ERY TENANT IN PRIC	R TENANT SPACE	, MINOR SITE
MPROVEMENTS IUMBER OF DWELLING UNITS _	0			A 1219 ACRES
DATE CONSTRUCTION OR ALTE	RATION IS EXPECTED TO	START ILLY 202	DOMINIERCIAL ARE	A 1.310 ACKES
RECEIVING CANAL FOR PROJEC				
			Zullin news	
ROPERTY OWNER: FLAMINGO		TMENTS, LLC (ALBER	TO MICHA BUZAL	1)
DDRESS 336 E. DANIA BEACH				
	STATE _FL	ZIP <u>33004</u>	PHONE S	954-505-5501
MAIL NCLAVERO@DACAR.US	-			
EVELOPER: SAME AS ABOV	/F			
	STATE	ZIP	PHONE	
MAIL				
ROJECT ENGINEER: GREGOR				
DDRESS: 445 24TH STREET, SU	JITE 200	710		770 704 4440
ITY VERO BEACH MAIL GREG.WILFONG@KIMLEY		ZIP _ 32960	PHONE _	//2-/94-4119
S THE PERMITTEE AND/OR OW		SET FORTH ABOVE		D AND AGREE THAT
The use of or construction will	be in accordance with the detail	Is of the approved drawing	s) supporting this perm	nit; and if any changes are required,
same will be cleared with the Pl	LANTATION ACRES IMPROVEN	MENT DISTRICT in writing p	rior to initiating.	
	PROVEMENT DISTRICT will be n			pections. Ense to the PLANTATION ACRES
IMPROVEMENT DISTRICT.	us discharges due to permitte	a actions will be corrected	promptly at no expe	ense to the Plantation Acres
The area under permit will be n	naintained in a safe condition at	all times or equipment will b	e promptly removed fro	om the right of way of easement and
	nt will be restored to its original of			nation of the authorized use. ACRES IMPROVEMENT DISTRICT
	ht of way or easements will be pe		Jess of PLANTATION /	ACRES IMPROVEMENT DISTRICT
As Permittee, will hold and save	e the PLANTATION ACRES IMP	ROVEMENT DISTRICT and		ss from any and all damages, claims
	reason of the construction, operative action of the construction operation			
regulation or requirement affect	ing the rights of other bodies or a	or privileges other than thos	e specified nerein, nor i	relieve from complying with any law,
	year with an additional 60 day	grace period. An extension	must be requested if	work is not completed during permit
period. To abide by the terms and cond	it a faith and the second			
To ablde by the terms and cond	litions of the permit.			
IGNED	11190		DAT	TE 1/28/2022
	Signature (if not the owner,	certify below)		- la al avea
HEREBY CERTIFY THAT I AM AM	NAUTHORIZED AGENT O	F THE OWNER: (Attacl	Letter of Authoriza	ation from Owner)
		TITLE		
OUNTY OF Broward				
OUNTY OF Brownero	011.111.1	1 1. 0		
efore me personally appeared	LIBERTO MICH.	burali 20 Ho	SIDERT of	ntrant vinte avainat
be known to be the person(s) des	scribed in or who has produ	ced .	as identification	n and who executed the
pregoing instrument and acknowled	ged before me that	arto Mich Billeexe	cuted said instrume	nt for the purpose expressed.
	north			2022
ITNESS my hand and official seal	this	day d	f January	Jadd .
, h	MIN. Lat	N.	Ma ha	Seita
y Commission Expires:	unga Soula	ma	Myga	Junjan
	NOTARY PUBLIC		/ Type,	Print or Stamp Name
his permit does not become valid u			CRES IMPROVEN	IENT DISTRICT. This permit
ill expire one year, to the day, from	i the date signed by the Cha	airman.		
IGNED	DATE	DE	RMITOSEEDE	NUMBER C2111.01
VPAID/FORMS/Applications/DISTPER2.PAI	UAIE			rev. 04/02/98 SFP8
		I AND A AND A MAR I A MONAL	UNI DODANE SOUTHER	
		November 12, 2020	EXPIRE	
		CZOZ 'ZL JOQUION :	EXPIRES	
		VRA SANTAL	WA COW	and the second se

Action Required:	Status Update	
Item Description:	Pump Station Number 3 Rehabilitation	
PAID Number:	<u>D1707.01-3</u>	
Attachments:	None	
Summary:	 Contractor has provided all of the required shop drawings, which have The Contractor has informed us that the previous construction start d delayed due to an international material shortage of large diameter duc anticipated to be at the end of May or beginning of June. 	ate of March 14 th 2022, has been
Prepared by: <u>BMP</u>	Date: <u>3/14/2022</u>	2022-03-24 20-PAID Pump No 3 Staff Report.wpd

Action Required:	Update
Item Description:	20-YR Needs Analysis
PAID Number:	<u>D2109.01</u>
Attachments:	None
Summary:	Our office is currently preparing this item and will be submitting the above mentioned stormwater analysis on behalf of PAID to Broward County by June 30th, 2022.
Comments:	
Prepared by: <u>BMP</u>	Date: 3/14/2022 2022-03-24 D2109.01 20-Year Needs Analysis Staff Report.wp

Action Required:	Board Discussion
Item Description:	FP&L Poles & Guy Wires Swale Obstruction Evaluation
PAID Number:	<u>D2201.01</u>
Attachments:	None
Summary:	This item has been placed on the Agenda for discussion.
Recommendation:	N/A

Comments:

Prepared by: <u>BMP</u> Date: <u>3/14/2022</u>

2022-03-24 FP&L Guy Wire Engineer Staff Report.wpd

Action Required:	Board Discussion				
Item Description:	PAID Participation with the City of Plantation Funding for Improvements				
PAID Number:	<u>D2201.01</u>				
Attachments:	None				
Summary:	This item has been placed on the Agenda for discussion.				

Recommendation:	N/A	
Comments:		
Prepared by: <u>BMP</u>	Date: <u>3/14/2022</u>	2022-03-24 Funding For Improvements Engineer Staff Report.wpd

Action Required: Discussion

Item Description: Permit Activity Summary P.A.I.D. Number: D9408.02 & D9408.03 Attachments: None Summary: **Approved Building Permits** No. Name Address PAID No. 1. Loriga (Pool) 11310 NW 28th Court B2101.01 1200 NW 114th Avenue 12280 NW 23rd Street 11821 NW 27th Court 2. Gonzalez (House) B2106.01 Dubreuze (House) 3. B1310.01 4. Hessing (Pool) B1802.02 Bohl (Fence/Driveway) 11800 NW 5th Street 5. B0611.01 12350 NW 4th Street 6. Blocker (House) B2201.01 11630 NW 25th Street 7. Meneses (Fence) B9206.12 11421 NW 27th Court B1804.02 8. Waserman (Driveway) 9. Ferrus (House) 11301 N Mount Vernon Drive B0606.05

- **Summary:** Approved Certificates of Occupancy
 - 1. Rhino Homes LLC (House)

12351 NW 5th Street

B1507.01

Prepared by: HMS Date: 03/10/2022

J:\PAID\Projects (D)\1994\D9408.02-Approved Building Permits\WP\D9408.02 STAFF REPORT 2022-03-24.wpd

Action Required	: Discussion	Discussion					
Item Description	: Notices of Violation Summary						
P.A.I.D. Number:	<u>D9611.01</u>	<u>D9611.01</u>					
Attachments:	None						
Summary: The following is a summary of the existing violations.							
Name	Address	Violation		Status			
ROBLES	11600 NW 21 st STREET	CONSTRUCTION W/O PERMIT		IN PROCESS OF COMPLYING			
ARTEAGA	12101 NW 27 TH COURT	CLEARING W/O PERMIT		IN PROCESS OF NOTIFYING			

Prepared by: <u>HMS</u> Date: <u>03/15/2022</u>

J:\PAID\Projects (D)\1996\D9611.01-Violation Summary\WP\2022-03-24 D6. Nov Activity.wpd